

1/ Concrete Panel
Elev. 34'-0"
1/ Concrete Panel
Elev. 30'-6"
1/ Concrete Panel
Elev. 28'-0"

MATERIAL CALCULATIONS

MATERIAL:	AREA:	%:
MASONRY - TEXTURED AND PAINTED CONC. PANEL	4,852 SF	100%
EIFS	0 SF	0%
TOTAL AREA	4,852 SF	100%

NOTE:
ROOF MOUNTED MECHANICAL EQUIPMENT IS SCREENED BY
PARAPET WALLS

Exterior Elevation (North)
Scale: 1/8" = 1'-0"

1/ Concrete Panel
Elev. 30'-6"
1/ Concrete Panel
Elev. 28'-0"

MATERIAL CALCULATIONS

MATERIAL:	AREA:	%:
MASONRY - TEXTURED AND PAINTED CONC. PANEL	6,737 SF	100%
EIFS	0 SF	0%
TOTAL AREA	6,737 SF	100%

NOTE:
ROOF MOUNTED MECHANICAL EQUIPMENT IS SCREENED BY
PARAPET WALLS

Exterior Elevation (West)
Scale: 1/8" = 1'-0"

1/ Concrete Panel
Elev. 34'-0"
1/ Concrete Panel
Elev. 31'-0"

MATERIAL CALCULATIONS

MATERIAL:	AREA:	%:
MASONRY - TEXTURED AND PAINTED CONC. PANEL	4,815 SF	100%
EIFS	0 SF	0%
TOTAL AREA	4,815 SF	100%

NOTE:
ROOF MOUNTED MECHANICAL EQUIPMENT IS SCREENED BY
PARAPET WALLS

Exterior Elevation (South)
Scale: 1/8" = 1'-0"

1/ Steel Fascia
Elev. 39'-4"
1/ Concrete Panel
Elev. 34'-0"
1/ Concrete Panel
Elev. 31'-0"

MATERIAL CALCULATIONS

MATERIAL:	AREA:	%:
MASONRY - TEXTURED AND PAINTED CONC. PANEL	3,912 SF	76.9%
MASONRY - WOOD LOOK SYNTHETIC STONE VENEER	530 SF	10.4%
MASONRY - BRICK VENEER	648 SF	12.7%
EIFS	0 SF	0%
TOTAL AREA	5,090 SF	100%

NOTE:
ROOF MOUNTED MECHANICAL EQUIPMENT IS SCREENED BY
PARAPET WALLS

Exterior Elevation (East)
Scale: 1/8" = 1'-0"

TOTAL AREA THIS ELEVATION EXCLUDING GLAZING, DOORS, ROOFS, OR AWNINGS: 4,786 SF

*NOTE: ALL HVAC EQUIPMENT TO BE ROOF MOUNTED AND SCREENED
BY BUILDING PARAPET WALL

TOTAL AREA THIS ELEVATION EXCLUDING GLAZING, DOORS, ROOFS, OR AWNINGS: 5,454 SF

TOTAL AREA THIS ELEVATION EXCLUDING GLAZING, DOORS, ROOFS, OR AWNINGS: 4,786 SF

TOTAL AREA THIS ELEVATION EXCLUDING GLAZING, DOORS, ROOFS, OR AWNINGS: 5,090 SF

1/ Trash Screens, Typical
Elev. 8'-0"
Finished Grade
Elev. 0'-0"

Typical Trash Screenwall
Scale: 1/8" = 1'-0"

CUSTOMER PICK-UP AREA
SHOWN SKEWED
RECEIVING AREA
SHOWN SKEWED

EXTERIOR TRUCK
SCREENWALL
(SHOWN SKEWED)
INTERIOR TRUCK
SCREENWALL
(SHOWN SKEWED)

MATERIAL SCHEDULE

NO:	DESCRIPTION:
A1	ALUMINUM FRAMED STOREFRONT, COLOR TO BE BLACK
A2	ALUMINUM COPING & STANDING SEAM ROOFING, COLOR TO BE BLACK
M1	CONCRETE TILT WALL, ACRYLIC TEXTURED COATING, SHERWIN WILLIAMS SW7028
M2	CONCRETE TILT WALL, ACRYLIC TEXTURED COATING, SHERWIN WILLIAMS SW7024
M3	BRICK VENEER, HOME ZONE BLEND BY BLACKSON BRICK, NO SUBSTITUTIONS
M4	SIMULATED WOOD MASONRY VENEER
M5	CAST STONE CAP UNITS
M6	PAINTED CMU TRUCK AND TRASH SCREEN WALLS, SHERWIN WILLIAMS SW7026
S1	STEEL CANOPY FRAMING AND SIGNAGE SUPPORT, COLOR TO BE BLACK
S2	STEEL CHANNEL WINDOW FRAME ACCENTS, COLOR TO BE BLACK
S3	STEEL DOORS, OVERHEAD DOORS, SHERWIN WILLIAMS SW7024
S4	STEEL DOORS, OVERHEAD DOORS, SHERWIN WILLIAMS SW7026
S5	CUSTOMER PICK-UP DOORS, SHERWIN WILLIAMS SW7026