

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

PAVING AND DRAINAGE

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|---|-----------------------|-----------------|
| 1 | 1 | LS | For mobilization and move-in (5% max) complete and in place for the Lump Sum of <u>Two Hundred Twenty Thousand Dollars and No Cents per Lump Sum</u> | \$ 220,000.00 | \$220,000.00 |
| 2 | 11 | AC | Preparing Right of Way, including all appurtenant work and tree removal, complete in place, for the some of <u>Twenty Four Thousand Dollars and No Cents per Acre</u> | \$ 24,000.00 | \$264,000.00 |
| 3 | 12 | MO | Implement traffic control, signing, and barricading along with all other incidentals necessary for the Lump Sum of <u>Five Thousand Dollars and No Cents per Month</u> | \$ 5,000.00 | \$60,000.00 |
| 4 | 1 | LS | Erosion Control for all disturbed areas, including inlet sediment barriers and all incidentals for the Lump Sum of <u>Twenty Two Thousand Dollars and No Cents per Lump Sum</u> | \$ 22,000.00 | \$22,000.00 |
| 5 | 51 | SY | Remove and dispose of existing reinforced or non-reinforced concrete street, alley, sidewalk, ramp, or curb including all incidentals for the sum of <u>Ten Dollars and No Cents per Square Yard</u> | \$ 10.00 | \$510.00 |
| 6 | 75 | LF | Remove and dispose of existing traffic barricades including all incidentals for the sum of <u>Ten Dollars and No Cents per Linear Foot</u> | \$ 10.00 | \$750.00 |
| 7 | 1 | EA | Remove 24 inch safety end treatment for the sum of <u>Five Hundred Dollars and No Cents per Each</u> | \$ 500.00 | \$500.00 |
| 8 | 35 | CY | Remove variable depth stone rip-rap for the sum of <u>Twenty Dollars and No Cents per Cubic Yard</u> | \$ 20.00 | \$700.00 |

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|---|-----------------------|-----------------|
| 9 | 217 | LF | Saw cut for the removal of existing reinforced or non-reinforced concrete street, alley, sidewalk, ramp, or curb including all incidentals for the sum of <u>Five Dollars and No Cents per Linear Foot</u> | \$ 5.00 | \$1,085.00 |
| 10 | 13,356 | CY | Unclassified roadway excavation including all clearing, hauling and disposal of surplus for the sum of <u>Six Dollars and No Cents per Cubic Yard</u> | \$ 6.00 | \$80,136.00 |
| 11 | 23,243 | CY | Embankment (TY C1), complete in place, for the sum of <u>Three Dollars and No Cents per Cubic Yard</u> | \$ 3.00 | \$69,729.00 |
| 12 | 5,349 | SY | Furnish and install block sodding, including 4 inches of top soil and watering until established, including all incidentals for the sum of <u>Three Dollars and No Cents per Square Yard</u> | \$ 3.00 | \$16,047.00 |
| 13 | 11,271 | SY | Seeding, including fertilizer and sprinkling until the project is accepted, complete and in place for the sum of <u>No Dollars and Sixty Cents per Square Yard</u> | \$ 0.60 | \$6,762.60 |
| 14 | 15,014 | SY | Pulverizing, mixing and compacting 6 inch thick lime subgrade compacted to 95% proctor density for the sum of <u>Four Dollars and No Cents per Square Yard</u> | \$ 4.00 | \$60,056.00 |
| 15 | 270 | TONS | Hydrated Lime for subgrade treatment all according to the plans and specifications, complete and in place for the sum of <u>One Hundred Fifty Dollars and No Cents per Ton</u> | \$ 150.00 | \$40,500.00 |
| 16 | 13,903 | SY | Construct 9 inch Class C, 3600 psi, reinforced concrete street paving, including all incidentals for the sum of <u>Forty Eight Dollars and No Cents per Square Yard</u> | \$ 48.00 | \$667,344.00 |

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|---|-----------------------|-----------------|
| 17 | 2,391 | SY | Construct 6 inch Class C, 3600 psi, reinforced concrete hike and bike trail, including all incidentals for the sum of <u>Fifty Four Dollars and No Cents per Square Yard</u> | \$ 54.00 | \$129,114.00 |
| 18 | 416 | SY | Construct 4 inch Class C, 3600 psi, reinforced concrete sidewalk paving, including all incidentals for the sum of <u>Forty Seven Dollars and No Cents per Square Yard</u> | \$ 47.00 | \$19,552.00 |
| 19 | 1 | EA | Construct 4 inch Class C, 3600 psi, reinforced concrete barrier free ramp, including truncated domed pavers and all incidentals for the sum of <u>Two Thousand Three Hundred Dollars and No Cents per Each</u> | \$ 2,300.00 | \$2,300.00 |
| 20 | 80 | LF | Furnish and install 18 inch Class III RCP storm sewer pipe in variable depth trench, including all incidentals for the sum of <u>Sixty Dollars and No Cents per Linear Foot</u> | \$ 60.00 | \$4,800.00 |
| 21 | 1,190 | LF | Furnish and install 24 inch Class III RCP storm sewer pipe in variable depth trench, including all incidentals for the sum of <u>Seventy Eight Dollars and No Cents per Linear Foot</u> | \$ 78.00 | \$92,820.00 |
| 22 | 800 | LF | Furnish and install 30 inch Class III RCP storm sewer pipe in variable depth trench, including all incidentals for the sum of <u>One Hundred Five Dollars and No Cents per Linear Foot</u> | \$ 105.00 | \$84,000.00 |
| 23 | 388 | LF | Furnish and install 36 inch Class III RCP storm sewer pipe in variable depth trench, including all incidentals for the sum of <u>One Hundred Seventeen Dollars and No Cents per Linear Foot</u> | \$ 117.00 | \$45,396.00 |
| 24 | 507 | LF | Furnish and install 48 inch Class III RCP storm sewer pipe in variable depth trench, including all incidentals for the sum of <u>One Hundred Ninety Dollars and No Cents per Linear Foot</u> | \$ 190.00 | \$96,330.00 |

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|--|-----------------------|-----------------|
| 25 | 12 | EA | Construct 20 foot, concrete recessed curb inlet including all excavation, reinforcement, backfilling and all other incidentals for the sum of <u>Six Thousand Five Hundred Dollars and No Cents per Each</u> | \$ 6,500.00 | \$78,000.00 |
| 26 | 1,660 | CY | Unclassified channel excavation including all clearing, hauling and disposal of surplus for the sum of <u>Ten Dollars and No Cents per Cubic Yard</u> | \$ 10.00 | \$16,600.00 |
| 27 | 662 | CY | Construct 5 inch thick reinforced 2000 psi concrete rip-rap on a sloped surface for the sum of <u>Four Hundred Twenty Five Dollars and No Cents per Cubic Yard</u> | \$ 425.00 | \$281,350.00 |
| 28 | 37 | SY | Furnish and install 18 inch Gabion blanket, wire, fiber fabric, rock of the thickness and specifications shown in the plans, complete and in place for the sum of <u>Two Hundred Dollars and No Cents per Square Yard</u> | \$ 200.00 | \$7,400.00 |
| 29 | 3 | EA | Furnish and install pre-formed pavement marking words, including all incidentals for the sum of <u>Four Hundred Twenty Five Dollars and No Cents per Each</u> | \$ 425.00 | \$1,275.00 |
| 30 | 3 | EA | Furnish and install pre-formed pavement marking symbols, including all incidentals for the sum of <u>Three Hundred Ten Dollars and No Cents per Each</u> | \$ 310.00 | \$930.00 |
| 31 | 1,530 | LF | Furnish and install 4 inch white broken pavement markings and all other incidentals necessary for the sum of <u>One Dollar and No Cents per Linear Foot</u> | \$ 1.00 | \$1,530.00 |
| 32 | 588 | LF | Furnish and install 4 inch solid yellow pavement markings and all other incidentals necessary for the sum of <u>One Dollar and No Cents per Linear Foot</u> | \$ 1.00 | \$588.00 |

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|--|-----------------------|-----------------|
| 33 | 702 | LF | Furnish and install 8 inch solid white pavement markings and all other incidentals necessary for the sum of <u>Two Dollars and No Cents per Linear Foot</u> | \$ 2.00 | \$1,404.00 |
| 34 | 610 | LF | Furnish and install 12 inch solid yellow pavement markings and all other incidentals necessary for the sum of <u>Three Dollars and No Cents per Linear Foot</u> | \$ 3.00 | \$1,830.00 |
| 35 | 588 | EA | Furnish and install traffic buttons (TY C) and all other incidentals necessary for the sum of <u>Four Dollars and No Cents per Each</u> | \$ 4.00 | \$2,352.00 |
| 36 | 239 | EA | Furnish and install reflective pavement markers (TY II C-R) and all other incidentals necessary for the sum of <u>Four Dollars and No Cents per Each</u> | \$ 4.00 | \$956.00 |
| 37 | 11 | EA | Furnish and install small roadside signs and all other incidentals necessary for the sum of <u>Four Hundred Thirty Dollars and No Cents per Each</u> | \$ 430.00 | \$4,730.00 |
| 38 | 1,604 | SY | Furnish and install Contech Landlok (C2) erosion control blanket and anchors, complete and in place for the sum of <u>Two Dollars and No Cents per Square Yard</u> | \$ 2.00 | \$3,208.00 |
| 39 | 150 | LF | Furnish and install metal beam guard rail fence including all incidentals for the sum of <u>Twenty Six Dollars and Fifty Cents per Linear Foot</u> | \$ 26.50 | \$3,975.00 |
| 40 | 2 | EA | Furnish and install metal beam guard rail fence thrie-beam transitions including all incidentals for the sum of <u>Two Thousand Three Hundred Dollars and No Cents per Each</u> | \$ 2,300.00 | \$4,600.00 |

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|---|-----------------------|-----------------|
| 41 | 2 | EA | Furnish and install metal beam guard rail end treatments including all incidentals for the sum of <u>Three Thousand Five Hundred Dollars and No Cents per Each</u> | \$ 3,500.00 | \$7,000.00 |
| 42 | 2 | EA | Furnish and install crash cushion attenuator including all necessary incidentals for the sum of <u>Twenty Thousand Dollars and No Cents per Each</u> | \$ 20,000.00 | \$40,000.00 |
| 43 | 1,795 | LF | Furnish and install complete trench safety for storm sewer installations including all incidentals for the sum of <u>Five Dollars and No Cents per Linear Foot</u> | \$ 5.00 | \$8,975.00 |

TOTAL PAVING AND DRAINAGE:

\$2,451,134.60

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

WATER

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|---|-----------------------|-----------------|
| 1 | 2 | EA | Remove existing 12 inch water line plug and connect proposed 12 inch line to existing, complete in place for the sum of <u>Two Thousand Five Hundred Dollars and No Cents per Each</u> | \$ 2,500.00 | \$5,000.00 |
| 2 | 2.40 | TONS | Furnish and install 350 psi cement lined poly-wrapped ductile iron fittings with restraining glands for water mains including all incidentals for the sum of <u>Seven Thousand Five Hundred Dollars and No Cents per Ton</u> | \$ 7,500.00 | \$18,000.00 |
| 3 | 32 | LF | Furnish and install 6 inch DR-18 PVC Class 150 water pipe including all incidentals for the sum of <u>Sixty Four Dollars and No Cents per Linear Foot</u> | \$ 64.00 | \$2,048.00 |
| 4 | 217 | LF | Furnish and install 8 inch DR-18 PVC Class 150 water pipe including all incidentals for the sum of <u>Forty Six Dollars and No Cents per Linear Foot</u> | \$ 46.00 | \$9,982.00 |
| 5 | 2,329 | LF | Furnish and install 12 inch DR-18 PVC Class 150 water pipe including all incidentals for the sum of <u>Sixty Nine Dollars and No Cents per Linear Foot</u> | \$ 69.00 | \$160,701.00 |
| 6 | 157 | LF | Furnish and install 20 inch steel casing pipe including all incidentals for the sum of <u>Four Hundred Seventy Five Dollars and No Cents per Linear Foot</u> | \$ 475.00 | \$74,575.00 |
| 7 | 6 | EA | Furnish and install 6 inch gate valve including box, stack and concrete pad (where called for) along with all incidentals for the sum of <u>Nine Hundred Dollars and No Cents per Each</u> | \$ 900.00 | \$5,400.00 |
| 8 | 2 | EA | Furnish and install 8 inch gate valve including box, stack and concrete pad (where called for) along with all incidentals for the sum of <u>One Thousand Three Hundred Dollars and No Cents per Each</u> | \$ 1,300.00 | \$2,600.00 |

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|--|-----------------------|-----------------|
| 9 | 6 | EA | Furnish and install 12 inch gate valve including box, stack and concrete pad (where called for) along with all incidentals for the sum of <u>Two Thousand Two Hundred Dollars and No Cents per Each</u> | \$ 2,200.00 | \$13,200.00 |
| 10 | 2 | EA | Furnish and install 8 inch restrained plug along with all incidentals for the sum of <u>Fifty Dollars and No Cents per Each</u> | \$ 50.00 | \$100.00 |
| 11 | 6 | EA | Furnish and install standard City of Allen fire hydrant of variable depth bury along with all incidentals for the sum of <u>Four Thousand Five Hundred Dollars and No Cents per Each</u> | \$ 4,500.00 | \$27,000.00 |
| 12 | 1 | EA | Furnish and install 2 inch vacuum-air release valve along with all incidentals for the sum of <u>Four Thousand Seven Hundred Fifty Dollars and No Cents per Each</u> | \$ 4,750.00 | \$4,750.00 |
| 13 | 2 | EA | Furnish and install 12 inch blow off valve including 12 inch ductile iron pipe and all incidentals for the sum of <u>Four Thousand Two Hundred Dollars and No Cents per Each</u> | \$ 4,200.00 | \$8,400.00 |
| 14 | 2,735 | LF | Furnish and install complete trench safety for water installations including all incidentals for the sum of <u>Five Dollars and No Cents per Linear Foot</u> | \$ 5.00 | \$13,675.00 |
| 15 | 2 | EA | Furnish and install standard manhole lid including all incidentals for the sum of <u>Five Hundred Dollars and No Cents per Each</u> | \$ 500.00 | \$1,000.00 |
| 16 | 2 | EA | Adjust existing sanitary sewer manhole to proposed elevation noted in the plans including all incidentals for the sum of <u>Three Thousand Five Hundred Dollars and No Cents per Each</u> | \$ 3,500.00 | \$7,000.00 |

TOTAL WATER: \$353,431.00

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

SANITARY SEWER

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|--|-----------------------|-----------------|
| 1 | 1 | EA | Construct standard sealed 5 foot diameter precast or cast in place sanitary sewer manhole including all incidentals for the sum of <u>Thirteen Thousand Five Hundred Dollars and No Cents per Each</u> | \$ 13,500.00 | \$13,500.00 |
| 2 | 1 | EA | Construct standard 5 foot diameter precast or cast in place sanitary sewer manhole including all incidentals for the sum of <u>Twelve Thousand Dollars and No Cents per Each</u> | \$ 12,000.00 | \$12,000.00 |
| 3 | 440 | LF | Furnish and install 15 inch SDR-35 (ASTM D-3034) PVC sanitary sewer pipe including all trenching, embedment, backfill and incidentals necessary for the sum of <u>Eighty Dollars and No Cents per Linear Foot</u> | \$ 80.00 | \$35,200.00 |
| 4 | 100 | LF | Furnish and install 24 inch steel casing of 0.375 inch thickness including all incidentals for the sum of <u>Five Hundred Dollars and No Cents per Linear Foot</u> | \$ 500.00 | \$50,000.00 |
| 5 | 40 | CY | For 2000 psi concrete encasement cap for sanitary sewer mins, including all incidentals, for the sum of <u>One Hundred Dollars and No Cents per Cubic Yard</u> | \$ 100.00 | \$4,000.00 |
| 6 | 540 | LF | Furnish and install complete trench safety for sanitary sewer installations including all incidentals for the sum of <u>Ten Dollars and No Cents per Linear Foot</u> | \$ 10.00 | \$5,400.00 |
| 7 | 11 | CY | Construct 5 inch thick reinforced 300 psi concrete rip-rap on a sloped surface for the sum of <u>Five Hundred Dollars and No Cents per Cubic Yard</u> | \$ 500.00 | \$5,500.00 |
| 8 | 43 | SY | Furnish and install 18 inch Gabion blanket, wire, fiber fabric, rock of the thickness and specifications shown in the plans, complete and in place for the sum of <u>Two Hundred Dollars and No Cents per Square Yard</u> | \$ 200.00 | \$8,600.00 |

TOTAL SANITARY SEWER:

\$134,200.00

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

BRIDGE

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|---|-----------------------|-----------------|
| 1 | 442 | CY | Install cement stabilized backfill around bridge abutments along with all incidentals for the sum of <u>One Hundred Dollars and No Cents per Cubic Yard</u> | \$ 100.00 | \$44,200.00 |
| 2 | 82 | LF | Furnish and install 18 inch drill shaft including all incidentals for the sum of <u>Fifty Dollars and No Cents per Linear Foot</u> | \$ 50.00 | \$4,100.00 |
| 3 | 637 | LF | Furnish and install 36 inch drill shaft including all incidentals for the sum of <u>One Hundred Twenty Five Dollars and No Cents per Linear Foot</u> | \$ 125.00 | \$79,625.00 |
| 4 | 122 | CY | Construct Class C reinforced concrete abutments along with all incidentals for the sum of <u>Eight Hundred Dollars and No Cents per Cubic Yard</u> | \$ 800.00 | \$97,600.00 |
| 5 | 100.80 | CY | Construct Class C reinforced concrete bent caps along with all incidentals for the sum of <u>Nine Hundred Dollars and No Cents per Cubic Yard</u> | \$ 900.00 | \$90,720.00 |
| 6 | 34.80 | CY | Construct Class C reinforced concrete columns along with all incidentals for the sum of <u>One Thousand One Hundred Dollars and No Cents per Cubic Yard</u> | \$ 1,100.00 | \$38,280.00 |
| 7 | 20.20 | CY | Construct Class C reinforced concrete traffic rail foundation along with all incidentals for the sum of <u>Four Hundred Fifty Five Dollars and No Cents per Cubic Yard</u> | \$ 455.00 | \$9,191.00 |
| 8 | 24,525 | SF | Construct reinforced 4,000 psi concrete slab including all incidentals for the sum of <u>Sixteen Dollars and No Cents per Square Foot</u> | \$ 16.00 | \$392,400.00 |

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

| ITEM NO. | EST QNTY | UNIT | DESCRIPTION AND PRICE IN WORDS | UNIT PRICE IN FIGURES | EXTENDED AMOUNT |
|----------|----------|------|--|-----------------------|-----------------|
| 9 | 225.60 | CY | Construct 13 inch thick reinforced 4,000 psi concrete approach slab including all incidentals for the sum of <u>Five Hundred Dollars and No Cents per Cubic Yard</u> | \$ 500.00 | \$112,800.00 |
| 10 | 3,128.72 | LF | Furnish and install precast prestressed concrete girders type TX40 along with all incidentals for the sum of <u>One Hundred Twenty Five Dollars and No Cents per Linear Foot</u> | \$ 125.00 | \$391,090.00 |
| 11 | 1,336 | LB | Furnish and install stl steel (non-bridge) along with all incidentals for the sum of <u>Ten Dollars and No Cents per Pound</u> | \$ 10.00 | \$13,360.00 |
| 12 | 598.40 | LF | Furnish and install combination rail type C402 (SLOTTED) (MOD) along with all incidentals for the sum of <u>One Hundred Twenty Five Dollars and No Cents per Linear Foot</u> | \$ 125.00 | \$74,800.00 |
| 13 | 510 | LF | Furnish and install pedestrian rail type PR3 (MOD) along with all incidentals for the sum of <u>One Hundred Ninety Five Dollars and No Cents per Linear Foot</u> | \$ 195.00 | \$99,450.00 |
| 14 | 232.80 | LF | Furnish and install permanent, cast-in-place, F-Shape, Type 1 concrete safety barrier including all incidentals for the sum of <u>One Hundred Five Dollars and No Cents per Linear Foot</u> | \$ 105.00 | \$24,444.00 |
| 15 | 325 | LF | Furnish and install 4" electrical conduit including all incidentals for the sum of <u>Fifty Seven Dollars and No Cents per Linear Foot</u> | \$ 57.00 | \$18,525.00 |
| 16 | 2 | EA | Furnish and install Type A Ground Box including all incidentals for the sum of <u>One Thousand Three Hundred Dollars and No Cents per Each</u> | \$ 1,300.00 | \$2,600.00 |

TOTAL BRIDGE: \$1,493,185.00

RIDGEVIEW DRIVE EXTENSION - COTTONWOOD CREEK TO CHELSEA BLVD
BID# 2017-7-109 CIP# ST1701

PROPOSAL SUMMARY

TOTAL PAVING AND DRAINAGE \$2,451,134.60

TOTAL WATER \$353,431.00

TOTAL SANITARY SEWER \$134,200.00

TOTAL BRIDGE \$1,493,185.00

TOTAL BID **\$4,431,950.60**

The Contractor hereby agrees to commence work within Ten (10) days after the date written notice to do so shall have been given to him, and to be substantially complete by August 10, 2018, subject to such extensions of time as are provided by the General and Special Conditions.

The work proposed to be done shall be accepted when fully completed and finished in accordance with the plans and specifications.

In the event of the award of a contract to the undersigned, the undersigned will furnish a Performance Bond and Payment Bond for the full amount of the contract.

The undersigned certifies that the bid prices contained in this proposal have been carefully checked and are submitted as correct and final.

NOTE: Unit and lump sum prices must be shown in words and figures for each item listed in the proposal and in the event of discrepancy the words shall control.

Receipt is hereby acknowledged for the following addenda to the contract documents:

| | | | |
|----------------------|-----------------------------|----------|-----------------------------|
| Addendum No. 1 dated | <u>8/18/2017</u> | Received | <u>8/18/2017</u> |
| Addendum No. 2 dated | <u>8/18/2017</u> | Received | <u>8/18/2017</u> |
| Addendum No. 3 dated | <u> </u> | Received | <u> </u> |
| Addendum No. 4 dated | <u> </u> | Received | <u> </u> |
| Addendum No. 5 dated | <u> </u> | Received | <u> </u> |

The undersigned, in submitting this bid proposal and their endorsement of same, represents that they are authorized to obligate their firm, that they have read this entire bid proposal package, is aware of the covenants contained herein and will abide by and adhere to the expressed requirements. Submittals will be considered as being responsive only if entire Bid Package plus any/all attachments is returned with all blanks completed.

Total Amount Bid: \$4,431,950.60

Mario Sinacola & Sons Excavating, Inc.

Contractor

By: Michael Sinacola

(please print name)

Signature: 

Title: Vice President

Seal and Authorization
(If a Corporation)

10950 Research Road

Address

Frisco, Texas 75033

City, County, State and Zip

214-387-3900

Telephone

214-387-3940

Fax No.

E-Mail Address: JLarson@MarioSinacola.Com